

Spec. NoEP:PVM:EQS:01Rev. No01

Page **1** of **6**

Tender Ref. EP: MM: SPV: NIT: 01 Tender Date 04.12.2015

ADDENDUM / CORRIGENDUM Issued FOR PURCHASE SPECIFICATION FOR SOLAR PHOTOVOLTAIC MODULE MANUFACTURING LINE SPEC No: EPD-PVM-EQS-01 Rev 00 dated 3.12.2015 pursuant to the pre-bid meeting held on 11.12.2015. Vendors / bidders shall consider these changes while formulating their offers.

S.No	NIT Spec Ref	Original Clause of NIT	Amended Clause of the NIT
1	Pg No 3 , Pre- Qualification Criteria	The turnkey supplier shall necessarily meet the following pre-qualification criteria.	The turnkey or consortium supplier shall necessarily meet the following pre- qualification criteria.
2	Pg No 3 , Pre- Qualification Criteria	Turnkey bidder shall have the experience of turnkey installations of Solar PV Module Manufacturing line(s)	Turnkey / consortium bidder shall have the experience of turnkey installations of Automated Solar PV Module Manufacturing line(s)
3	Pg No 3 , Pre- Qualification Criteria 2.(i)	Of not less than 500 MW cumulative capacity during the period from 01.12.2010 to 30.11.2015, of which there shall be minimum 3 installations of manufacturing lines of minimum 100 MWp Annum capacity.	Of not less than 500 MW cumulative capacity during the period from 01.12.2010 to 30.11.2015, of which there shall be minimum 3 installations of automated manufacturing lines of minimum 100 MWp annum capacity.
4	Pg No 3 , Pre- Qualification Criteria 2.(ii)	With relevant business presence in India and having a reference of at least one (1) Turnkey Solar PV module manufacturing line installation in India working satisfactorily.	With relevant business presence in India and having a reference of at least one (1) automated Turnkey Solar PV module manufacturing line installation in India working satisfactorily.
5	Pg No 3 , after Pre- Qualification Criteria 2.(iii)	Documentary evidence for the above shall be provided in the form of the satisfactory certificate issued by the customer, purchase order, commissioning certificate and the performance certificate from the customers.	Documentary evidence for the above shall be provided in the form of the satisfactory certificate issued by the customer, purchase order, commissioning certificate and the Performance certificate from the customers. Consortium bidders must submit the 'Memorandum of Understanding' entered between the members for meeting the qualification criteria, conformance to the technical specifications and the period of understanding till the completion of warranty.
6	Page No 4 , Pt No 4	Turnkey supplier shall be the original equipment manufacturer or are their authorized company / organization for at least one of the following process equipment for Solar PV Module manufacturing. 1. Automatic Tabber & Stringer 2. Automatic Layup station	Turnkey / Consortium supplier shall be the original equipment manufacturer or are their authorized company / organization for at least one of the following process equipment for Solar PV Module manufacturing. 1. Automatic Tabber & Stringer 2. Automatic Layup station
7	Page No 4 , Pt No 5	Turnkey supplier shall take full responsibility for successful integration, performance proving,	Turnkey / Consortium supplier shall take full responsibility for successful integration,



Spec. NoEP:PVM:EQS:01Rev. No01

Page 2 of 6

		warranty, TS & M contract, AMC for	performance proving, warranty, TS & M
		the entire Solar PV module	contract, AMC for the entire Solar PV module
		manufacturing line.	manufacturing line.
8	Page No 4, Pt	All Major equipments as mentioned in	The 'Automatic Tabber & Stringer' and
	No 6	S.No 3 above shall bear the	"Automatic Layup station with 6 axis robot"
		'Conformite Europeenne (CE)'	shall bear the 'Conformite Europeenne (CE)'
		Marking. The relevant certificates and	Marking. The relevant certificates and
		technical documentation shall be	technical documentation shall be made
		made available in the techno-	available in the techno-commercial bid.
0		commercial bid.	
9	Page No 4, Pt	Overall line yield:≥99% (excluding	Overall line yield: Minimum 99% (excluding
10	No $2(a)$	electrical rejects)	electrical rejects & process rework)
10	Page No 4, Pt	Technical line availability : $\geq 95\%$	Technical line availability: Minimum of 7260
	No 2(a)	with 24x / operation	Hrs per annum, producing 100 modules per
			hour for /2 cell module or 120 modules per
11	Daga Na 6	\mathbf{p}_{1}	nour for 60 cell module.
11	Page NO 0 Point 2 (b)	Find update 293% Plant Vield 290%	riant upume : winninum of /200 Hours per
12	$\frac{r \operatorname{Ont} 2 (0)}{\operatorname{Page no 6}}$	The equipment must be chosen to	The equipment must be chosen to deliver the
12	$\frac{1}{2} agc 100$	deliver the required minimum	required minimum throughput for each of the
	11105	throughput for each of the station. The	station. The detailed equipment specifications
		detailed equipment specifications are	are given in section 9. The number of
		given in section 9 The number of	equipment at each of the stage in the
		equipment shown is only indicative	automated module manufacturing line is
		and may vary according to through	indicated below.
		output of the equipment and line	
		configuration offered.	
13	Page no 7:	Auto EVA Cutting & Layup	Auto EVA Cutting & Layup : No of
	Point no 3	No of Equipment : 01 for 1 line	equipment 01 for 2 lines
		And No of equipment for 2 lines :	
		02 for 2 lines.	
14	Page no 7:	Bussing Station 06 inline stations per	Bussing Station 04 inline stations per line,
	Point no 4	line ,12 inline stations for 2 lines	08 inline stations for 2 lines
15	Page no 7:	EVA & Back sheet Layup Station 03	EVA & Back sheet Layup Station
	Point no 5	per line and 06 for 2 lines	02 per line and 04 for 2 lines
16	Page no 8:	Framing of panel laminate in	Framing of panel laminate in Aluminium
	Point no 11	Aluminium sections with corner block	sections with corner block Punching type
		Punching type securing.	securing. Loading of frame elements should
			also be Automatic.
17	Page no 8:	Hi Pot Tester	Not required separately as the specification of
	Point no 13		SUN SIMULATOR includes inbuilt hi pot
10			tester
18	Page no 8:	Xenon / LED lamp light source	Xenon / LED lamp light source evaluation of
	Point no 14	evaluation of module output with	module output with computer interface for
		computer interface for data	data acquisition and monitoring. In built
		acquisition and monitoring.	Iv tester for online hi-pot testing (Upto 5000
			v) with provision of time adjustment. Also
			capable of measuring insulation Resistance
10	Dece 9	Automotio Destaine et d' D'1	(upto 1000 v DC) & Continuity testing
19	Page no 8:	Automatic Packing station: Pick,	Automatic sorting & Packing station :
	Point no 15	overturn, stack and pallet loading of	Automated sorting based on pre-defined
			module wattage in 4 rating slabs with 4+2



Spec. NoEP:PVM:EQS:01Rev. No01Page 3 of 6

		the modules into carton box. Lift and	hing Pick overturn stack and pallet loading
		place for transport	of the modules into corton box. Lift and place
		prace for transport.	for the modules into carton box. Lift and place
20	D 0		
20	Page no 9:	To match above and minimum of	10 match above and minimum of 15 minute
	Point no 16	30 minute of buffer at the all critical	buffer at the following stations:
		stations	- Before Layup
			- After layup
			- Before Laminator
			- Before Framing
			However, the buffers at each station defined in
			section 9 shall also prevail.
21	Page no 9:	Panel repair station :02 per line and 04	Panel repair station :01 per line and 02 for 2
	Point no 18	for 2 lines	lines
	(D)		
22	Page no 11:	Laminate storage racks, EVA & Back	Laminate storage racks, EVA & Back sheet
	Point no 5b	sheet Storage Racks, Trolleys for	Storage Racks, Trolleys for manual material
		manual material Movement from one	movement from one station to other, manual
		station to other, manual repair station	repair station to automated line for string
		to automated line for string & panel	& panel repair etc., as appropriate for each of
		repair etc., as appropriate for each of	the line. Bids to indicate the technical
		the line. Bids to indicate the technical	details and quantity of such auxiliary
		details of such auxiliary equipment	equipment offered
		offered	equipment offered.
23	Page no ·11	Environment Test Chamber and its	Not Required / Not Applicable
23	Point No 7 1	specification	Not Required 7 Not Applicable
24	Page no ·12	Mechanical Load Tester Equipment	Not Required / Not Applicable
27	Point No 7 2	and its specification	Not Required 7 Not Applicable
25	Page no ·12	Gel Content Test Setun	Gel Content Test Setup : Bidders to provide
23	Point No 7 3	Ger Content Test Setup	the technical specifications and BOO of
	1 0mt 100 7.5,		offered instruments
26	Dega no 12	Solder Deal Strength tester	Solder Deal Strength tester : Didders to
20	Page II0.12 Doint No.7.4	Solder Feel Stieligtil tester	solder reel suchigui tester . Didders to
	Point No 7.4		provide the technical specifications of offered
27	D 10		TILL C C C C C C C C C C C C C C C C C C
27	Page no :12	EVA Pull Strength Tester	EVA Pull Strength Tester : Bidders to provide
	Point No 7.5		the technical specifications of offered
•			instruments.
28	Page no :15	Interconnect spacing: 26-78 mm. The	Interconnect spacing to suit the number of
	Point No 9.1	preset standard sizes may be defined	bus-bars as indicated in SI no. iii. The preset
		in the technical offer.	standard sizes may be defined in the technical
			offer.
29	Page no :15	Conveyor Direction : bi directional	Conveyor Direction : uni directional
	Point No 9.1		
	xiii		
30	Page no :17	Camera assisted alignment of the string	Camera or Optical sensor assisted alignment
	Point No 9.2		of the string
	xvi		C
31	Page no :17	Camera for string inspection	Camera for String Inspection : Not Required
	Point No 9.2	system with following features	<i>C</i> 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	xvi	a.High Resolution camera min 8	Additionally a suitable glass loading system
		Meganixel	shall also be included to feed both the lines
			and integrate with an automatic FVA cutting
			and lavan equipment in line
L			and ayup equipment in fine.



Spec. No EP:PVM:EQS:01

01

Rev. No

Page 4 of 6

32	Page no :17 Point No 9.3 ii	 b.Front and Backlight imaging and analysis with Software with failure diagnosis. c.The system should be able to Perform the identification of the broken cells, ribbon presence, ribbon misalignment, distance between cells and string dimensions The manual bussing station shall have multiple stations - minimum 6 work stations and 2 additional 	The manual bussing station shall have multiple stations - minimum 4 work stations per line and 1(one) additional stations for off- line repair per line
33	Page no :18	There Should be two stations for	There Should be 1 (one) stations for the each
34	Point No 9.5 Page no :19 Point No 9.7 xxii	the each of the manufacturing line. Standby vacuum pump shall be provided for uninterrupted operation	of the manufacturing line. 1 (one) standby vacuum pump shall be provided for uninterrupted operation as a mandatory spare. Preferred Make of Vacuum Pump : BUSCH
35	Page no :20 Point No 9.9	2 Nos online and 2 no. off-line Automatic film cutting machine for EVA and back sheet.	1 (one) No online automatic cutting & layup for both the lines combined and 2 no. off-line Automatic film cutting machine for EVA and back sheet
36	Page no :20 Point No 9.11	A fully automated framing station should perform the following operations: Automatic positioning of the laminated, trimmed and taped module panel, sunny side down, Placement of the four frame section on the pressing plates and automatic profile positioning via proximity sensors, Automatic Centring of the module in the fix reference, Gripping and lifting of the module to the framing level Frame application to the module and punching of the four corners for a tight fit by self-centring devices. It should have the option of adjustable panel dimensions and be able to handle both the 60 cell and 72 Cell Module of maximum size 2000x1000 mm.	A fully automated framing station should perform the following operations: Automatic positioning of the laminated, trimmed and taped module panel, sunny side down, Placement of the four frame section on the pressing plates and automatic profile positioning via proximity sensors, Automatic Centring of the module in the fix reference, Gripping and lifting of the module to the framing level Frame application to the module and punching of the four corners for a tight fit by self-centring devices. It should have the option of adjustable panel dimensions and be able to handle both the 60 cell and 72 Cell Module of maximum size 2000x1000 mm. Loading of frame elements should also be automatic.
37	Page no :20 Point No 9.12	Curing Station for assembled PV modules with Silicone Sealant :The bidders have to incorporate PV Module curing station / line for the minimum prescribed time (Approx. 2 Hours). The curing station may have environment controlled for accelerated curing. The curing station could be of tunnel type wherein the modules progressively move and get cured while passing through. The	Curing Station for assembled PV modules with Silicone Sealant :The bidders have to incorporate PV Module curing station / line for the minimum prescribed time (Approx. 2 Hours). The curing station may have environment controlled for accelerated curing. The curing station could be of tunnel type wherein the modules progressively move and get cured while passing through. The construction details for enclosure, temperature & humidity control and mechanical



Spec. NoEP:PVM:EQS:01Rev. No01Page 5 of 6

		construction details for enclosure, temperature & humidity control and mechanical movement of the modules shall be indicated in the Techno- Commercial offer.	movement of the modules shall be indicated in the Techno-Commercial offer. Construction of tunnel & climatic controls inside shall be under the scope of BHEL.
38	Page No :22 Point No : 9.14 ix	Specification of inbuilt Hi Pot tester was not Available	The IV tester shall have provision for online hi-pot testing (Upto 5000 V) with provision of time adjustment. Also capable of measuring Insulation Resistance (upto 1000 V DC) & Continuity testing.
39	Page No :22 Point No : 9.15	Automatic Module Sorting &Packing Station :An Automatic Sorting & Packing station for sorting and packing the PV modules in packing case as per the packing quantity and case parameters programmable. One number sorting & packing station shall receive modules from both the lines for sorting and packing.	Automatic Module Sorting & Packing Station : An Automatic Sorting & Packing station for sorting and packing the PV modules in packing case as per the packing quantity and case parameters programmable. One number sorting & packing station shall receive modules from both the lines for sorting and packing.The sorting facility shall have provision for 4 bins to sort the modules based on the wattage as evaluated in the IV tester on-line. 2 spare bins shall also be provided.
40	Page No : 23 Point No 11 (e)	Vendor has to provide requisite consumables / input materials for the purpose of demonstration and proving at their site.	Vendor has to provide requisite consumables for the purpose of demonstration and proving at their site.
41	Page No : 23 Point No 11 (f)(g) (h)	f. The safety circuits, alarms and interlocks shall be demonstrated. g. BHEL will bear the expenses for their personnel travel and stay for the pre-dispatch inspection.	 f) BHEL shall organize the input material viz., PV Cells and ribbons for the Tabber & Stringer and Lay-up station inspection at vendors works. For other stations, the input materials such as glass, EVA, backsheet, frame elements, corner blocks, junction box,silicone sealant etc., shall be organized by vendors at their works. The quantity of the material required, procedure and steps involved in the inspection and protocols if any shall be described in the technocommercial offer. g. The safety circuits, alarms and interlocks shall be demonstrated. h. BHEL will bear the expenses for their personnel travel and stay for the pre-dispatch inspection.
42	Page No : 27 Pont No 22	 General Terms & Conditions: i. The commercial terms of this tender shall be applicable for the future purchases of the spares/consumables/sub-systems and consumables for the equipment to be procured from the supplier. ii. Supplier shall confirm 	General Terms & Conditions: i. The commercial terms of this tender shall be applicable for the future purchases of the spares/consumables/sub-systems and consumables for the equipment to be procured from the supplier. ii. Supplier shall confirm adequacy of the equipment and accessories quoted for the



Spec. No	EP:PVM:EQS:01
Rev. No	01
Page 6 of 6	

adequacy of the equipment and	intended use of turnkey line. Any other
accessories quoted for the	requirement shall not be entertained later.
intended use of turnkey line.	iii. Any deviation from the BHEL
Any other requirement shall	specification shall be clearly brought out.
not be entertained later.	Otherwise, it is understood that BHEL
iii. Any deviation from the BHEL	specification is accepted in total and there is
specification shall be clearly	NIL deviation.
brought out. Otherwise, it is	iv. Supplier shall keep BHEL indemnified
understood that BHEL	against any damage during installation,
specification is accepted in	commissioning, repairs and maintenance of
total and there is NIL	the equipment. Personnel deputed at BHEL
deviation.	shall be covered by relevant statutory
iv. Supplier shall keep BHEL	provisions of the ESI/Workmen
indemnified against any damage	compensation Act or other acts as applicable.
during installation, commissioning,	v. The technical specifications & features
repairs & maintenance of the	indicated for the individual stations or
equipment. Personnel deputed at	turnkey automated line is the basic minimum.
BHEL shall be covered by relevant	However, for higher or superior features or
statutory provisions of	configuration provided / offered will not
ESI/Workmen compensation Act	carry any weightage while evaluating price
/otheracts as-applicable.	bids.